



NAC Executive Insights

Modularization vs. Stick-Built Readiness Strategy

Key Points

- **Strategy over Technique:** Modularization is a fundamental capital efficiency strategy, not just a different construction method.
- **Total Installed Cost (TIC) is King:** Modularization rarely reduces baseline material/fabrication costs; it wins on TIC by slashing expensive field labor and compressing the overall schedule.
- **Inviolable Decision Window:** The final modularization decision(s) must be locked by 15% design maturity (Front End Loading-2 (FEL-2)) to avoid prohibitive re-engineering costs.
- **Logistics is the "Hard Gate":** If logistics feasibility (clearances, marine/road access) scores poorly, the modular strategy is non-viable, regardless of labor or schedule advantages.
- **Structured, Weighted Diagnostic:** A metric-driven tool scoring readiness from 1–100 determines if modular is "Preferred (vs Stick-Built)" or "Mandatory," shifting the decision from technical possibility to capital mandate.

The Strategic Imperative of Modularization

In the current capital projects landscape, modularization is no longer just an alternative construction method; it is a fundamental capital efficiency¹ strategy which must be actively considered and evaluated very early on (FEL1). When deployed correctly, it re-allocates risk, compresses critical-path schedules, and insulates megaprojects from volatile local labor dynamics.

For industrial, commercial, and infrastructure assets, the execution spectrum is vast, spanning five distinct levels of structural density:

- **Pre-Assembly / Component Fabrication:** Simple pre-fabricated structural steel elements or small piping spools.
- **System Skids:** Integrated mechanical units featuring pumps, valves, and instrumentation (e.g., dosing skids).
- **E-Houses & Utility Modules:** Fully enclosed, pre-wired electrical control sub-stations, MCC buildings, and/or analyzer houses.


¹ Prieto, R. (2014) Capital Efficiency: Pull All the Levers; Construction Management Association of America (CMAA); 978-1-938014-08-6 (eBook); ISBN 978-1-938014-09-3 (Print)

- **Standard Process Modules:** Linear pipe racks and structural blocks weighing up to several hundred tons.
- **Mega/Super-modules:** Highly complex, integrated facilities weighting from 500 to 5,000+ tons, requiring deep-water maritime logistics, specialized heavy-haul transport, and Self-Propelled Modular Transporters (SPMTs).

Executive Rule: Modularization is rarely selected to reduce the baseline material fabrication cost. In fact, factory base prices can run higher due to structural reinforcement for transport and yard overhead. Instead, modularization wins on Total Installed Cost (TIC) by driving extreme field labor displacement and capturing significant schedule compression.

Structured Evaluation Framework: Cost, Schedule, and Governance

A disciplined evaluation requires balancing three core dimensions before project design maturity passes 10–15% (FEL-2). Past this gate, the engineering modifications required to switch execution strategies become prohibitively expensive.



A. Total Installed Cost (TIC) Formulas

To determine financial viability, the total financial advantage (Delta TIC) is modeled as:

$$\text{Delta TIC} = \text{TIC}_S - \text{TIC}_M$$

Where a positive Delta TIC indicates that modularization is financially superior.

1. Modular Total Installed Cost (TIC_M):

$$\text{TIC}_M = F + Y + L_f + T + I + C_M - TV$$

Where:

- **F** = Fabrication cost (modules, skids, e-houses structural base).
- **Y** = Yard amortization allocation = CapEx / (Amortization Years * Annual Output).
- **L_f** = On-site modular installation labor (significantly reduced field hours).
- **T** = Transport logistics (heavy-haul, ocean barge, SPMT leases, permits).
- **I** = Site integration, setting, crane lifting, and interconnecting hook-ups.
- **C_M** = Tight modular project contingency (typically 5–10% due to predictable yard environments).
- **TV** = Time-Value financial benefit derived from early commissioning.

2. Stick-Built Total Installed Cost (TIC_S):

$$\text{TIC}_S = M + L_s + I_s + C_S$$

Where:

- **M** = Raw materials and loose equipment delivered to site.
- **L_s** = Unmanaged or variable field labor hours (subject to local productivity factors).
- **I_s** = Site indirect costs (extensive scaffolding, temporary facilities, weather-delay mitigations).
- **C_S** = Elevated stick-built contingency (typically 10–20% to buffer weather and labor volatility).

B. Time-Value of Construction (TV) Formula

Time savings are often the single largest economic lever for modular adoption. The value captured through schedule compression is modeled as:

$$\text{TV} = (I_d + O_d + R) * \text{Delta } t$$

Where:

- **I_d** = Daily field indirect costs (e.g., scaffolding, temporary power, site management overhead).

- **O_d** = Owner's project management and governance overhead per day.
- **R** = Daily net operational revenue or production value generated by early facility startup.
- **Delta t** = Net calendar days saved by parallelizing factory fabrication with on-site civil works.

The Executive Modularization Risk Assessment Tool

Logistics Feasibility Hard Gate Note: The following metric-driven risk framework is used to screen capital assets. Logistics Feasibility operates as a strict 'Hard Gate'—if any logistics category receives a score of 1, the modular strategy cannot proceed, regardless of favorable labor economics.

Scoring Framework & Weighting Distribution

- **Category 1: Labor & Productivity Drivers (Weight: 25%)** - Evaluates geographic scarcity, wage differentials, and safety risk profiles.
- **Category 2: Logistics & Envelope Feasibility (Weight: 20%)** - The Hard Gate. Assesses clearances, weight boundaries, and transport routes.
- **Category 3: Design Maturity & Standardization Potential (Weight: 20%)** - Rates scope stability and structural repeatability.
- **Category 4: Site Constraints & Environmental Factors (Weight: 15%)** - Examines physical space boundaries and weather windows.
- **Category 5: Schedule Criticality & Revenue Impact (Weight: 10%)** - Quantifies market window pressures and capital delay costs.
- **Category 6: Alignment, Capability & Governance (Weight: 10%)** - Evaluates project team and contractor maturity.

Each individual criterion within the categories is scored from 1 (Highly Infeasible / Prohibitive for Modular) to 5 (Highly Ideal / Compelling for Modular).

$$\text{Readiness Score} = \text{Sum} [(\text{Sum of Category Criteria Scores} / 25) * 100 * \text{Category Weight}]$$

Executive Interpretation Bands

- **Score >= 80: Modularization Mandatory.** Clear economic drivers, secure logistics, and high time-value yield. Freeze designs and mandate modular deployment in EPC tenders immediately.
- **Score 60-79: Modularization Advantageous.** Benefits outweigh baseline risks. Proceed with modular execution while funding detailed logistics simulations and strict engineering change boards.
- **Score 40-59: Modularization Conditional.** Hybrid potential. Limit modularization to targeted system skids, pipe racks, or e-houses while stick-building primary structures.
- **Score < 40: Stick-Built Preferred.** Prohibitive logistics, fluid designs, or adequate local labor markets. Modularization will inflate TIC.

Worked Examples

Four examples of application of this modularization risk assessment tool have been provided for an infrastructure (Appendix A), LNG (Appendix B), mining (Appendix C) and AI data center (Appendix D) projects. Values are for illustration only.

The risk assessment findings are summarized in the next section.

Comparative Executive Summary Dashboard

The cross-industry assessment demonstrates that modularization suitability depends on specific project constraints rather than asset type alone.

Project Scenario	Final Score	Strategy Classification	Dominant Financial Lever	Primary Execution Risk
US Cable-Stayed Bridge (Hudson River)	69.2	Modularization Advantageous	Site Indirects (I_s) via marine crane deployment over water.	Union Jurisdictions regarding off-site structural steel assembly.
LNG Export Plant (US Gulf Coast)	86.8	Modularization Mandatory	Field Labor Displacement (L_f) to offset local craft labor constraints.	Global Shipping Delays impacting critical-path transit schedules.
Iron Ore Complex (Western Australia)	81.2	Modularization Mandatory	Labor Productivity (L_s) avoiding remote outback FIFO costs.	Inland Road Clearances along the 400km transport route.
AI Hyper Data Center (Austin, Texas)	70.2	Modularization Advantageous	Time-Value (TV) driven by immediate computing lease revenue.	Late Scope Changes from shifting technology specifications.

The Executive Insight on Economic & Schedule Trade-offs in Modular vs Stick-Built Execution showed the economic advantage for each of the above four examples. The chart below compares the Risk Assessment score and the economic advantage for the four examples.

Comparison - Economic Advantage & Readiness Risk Assessment		
Example	Executive Insight - Economic Trade-Offs	Executive Insight - Readiness Risk Assessment
A - Infrastructure - US Cable-Stayed Bridge (Hudson River)	\$117M net capital advantage	69.2
B - Industrial - LNG Plant (US Gulf Coast)	\$650M total economic advantage	86.8
C - Heavy Industrial - Iron Ore Complex (Western Australia)	\$90M net capital savings	81.2
D - Commercial - AI Hyper Data Center (Austin, Texas)	\$91M net capital advantage	70.2
		Risk Assessment Score
		Score 80 & above - Modularization Mandatory
		Score 60-79 - Modularization Advantageous
		Score 40-59 - Modularization Conditional
		Score below 40 - Stick-Built Preferred

Core Strategic Conclusions

- **Logistics Rules:** Marine access enables mega-scale modularization options (thousands of tons), whereas landlocked locations restrict projects to highway-compliant sub-system skids and e-houses.
- **Time and Revenue Dictate Strategy:** When early commissioning revenue (R) is high, modularization remains the preferred strategy even if baseline fabrication costs (F) exceed stick-built estimates.
- **Enforce Design Discipline:** Achieving successful modular delivery requires moving from an 'on-site evolution' approach to an industrialized manufacturing model, supported by design locks at the 15% project maturity gate

Appendix A

Infrastructure — US Cable-Stayed Bridge (Hudson River)

Project Context

A massive infrastructure replacement over a major shipping channel. High maritime traffic, complex environmental permitting, high local union labor costs, and variable northeast winter weather conditions.

Category	Criterion	Score	Operational Annotation / Executive Justification
1. Labor & Productivity (Weight: 25%)	Labor Availability	2	Metro New York region features dense, highly skilled union labor pools.
	Wage Differential	1	Northeast marine construction labor rates match or exceed specialized regional shipyard rates.
	Field Productivity	3	Water-based operations lower productivity due to wind, currents, and safety rules.
	Union Constraints	1	Rigid project labor agreements (PLAs); off-site fabrication faces stiff jurisdictional pushback.
	Safety Profile	5	Working at extreme heights over deep water; high exposure to drowning and falls.
	Category Subtotal	12/25	Weighted Value: $(12 / 25) * 25 = 12.00$
2. Logistics Feasibility (Weight: 20%)	Transport Envelope	5	Hudson River allows unrestricted overhead clearance and massive horizontal widths for barges.
	Route Constraints	5	Direct ocean access to East Coast fabrication yards via deepwater channels.
	Barge/Port Access	5	Active marine corridor with deepwater staging areas near the bridge tower footings.
	Heavy Lift/SPMT	5	Heavy marine shear-leg crane vessels (e.g., Left Coast Lifter) are available for large-tonnage lifts.

	Seasonal Risks	3	Winter icing and high-wind events create distinct scheduling gaps for heavy lifts.
	Category Subtotal	23/25	Weighted Value: $(23 / 25) * 20 = 18.40$
3. Design & Standard. (Weight: 20%)	Equipment Freeze	4	Structural components (stays, anchorages) are specified early in the design cycle.
	Repeatability	4	Highly uniform, repeating pre-cast concrete and structural steel deck sections.
	3D Model Maturity	5	Advanced 4D/5D structural BIM is standard practice for major modern bridge elements.
	Interface Complexity	3	Tolerances for cable-stay tensioning and structural match-casting are tight.
	Scope Lock Change	4	Public agency procurement rules firmly enforce structural design locks.
	Category Subtotal	20/25	Weighted Value: $(20 / 25) * 20 = 16.00$
4. Site & Climate (Weight: 15%)	Laydown Space	1	Severe landside constraints; no staging areas available along populated riverbanks.
	Working at Height	5	Major towers extend hundreds of feet up; modular pre-assembly significantly mitigates this risk.
	Extreme Climate	3	Exposed to severe winter storms, river icing, and high-velocity wind drafts.
	Environmental Restraints	5	Strict acoustic and turbidity limits protect sturgeon and river ecosystems during site work.
	Congestion Profile	2	High commercial and commuter marine traffic directly adjacent to active work zones.
	Category Subtotal	16/25	Weighted Value: $(16 / 25) * 15 = 9.60$
5. Schedule Criticality (Weight: 10%)	Critical Path Comp.	4	Accelerating bridge completion alleviates regional vehicle bottlenecks early.

	Commissioning Window	2	Non-revenue public infrastructure, but highly visible milestone dates driven by politicians.
	Market Urgency	1	Public utility model; no immediate commercial spot-market revenue capture.
	Shutdown Limits	2	Temporary channel closures are tightly restricted by the US Coast Guard.
	Cost of Delay	4	Public pressure and extended financing costs generate significant liquidated damages.
	Category Subtotal	13/25	Weighted Value: $(13 / 25) * 10 = 5.20$
6. Governance & Alignment (Weight: 10%)	Contract Readiness	4	Design-Build structures align clean, unified risk responsibilities to a single consortium.
	Change Control	4	Clear public agency engineering gate approval processes reduce scope creep.
	Modular Experience	4	Tier-1 marine contractors possess deep experience with pre-assembled deck segments.
	Yard Capability	4	Established, capable coastal shipyards and steel fabricators are active along the East Coast.
	Interface Management	4	Well-defined structural interfaces manage steel-to-concrete connection points cleanly.
	Category Subtotal	20/25	Weighted Value: $(20 / 25) * 10 = 8.00$

Weighted Diagnostic Calculation

Readiness Score = $12.00 + 18.40 + 16.00 + 9.60 + 5.20 + 8.00 = 69.2$

Strategic Executive Decision

Classification: Modularization Advantageous (Score: 69.2)

Executive Directive: Proceed with a hybrid modular marine execution model. Primary structural steel deck sections and rebar cages should be pre-assembled at off-site coastal yards, barged to the site, and lifted directly into place from the river. Tower construction will remain a sequential stick-built / slip-form operation due to local labor conditions and jurisdictional rules.

Appendix B

Industrial — LNG Plant (US Gulf Coast)

Project Context

A massive, multi-train greenfield LNG export terminal. The site features excellent deepwater maritime access but faces a highly constrained regional craft labor pool due to concurrent regional megaprojects.

Category	Criterion	Score	Operational Annotation / Executive Justification
1. Labor & Productivity (Weight: 25%)	Labor Availability	5	Extreme local scarcity of critical cryogenic pipe welders and E&I technicians.
	Wage Differential	4	International modular yards (e.g., APAC) offer significant cost-per-hour labor advantages.
	Field Productivity	5	Local Gulf Coast field productivity factors routinely degrade below a 0.8 baseline.
	Union Constraints	4	Open-shop region, but high competition for workers creates high wage escalation.
	Safety Profile	5	High exposure risks involving intricate overhead cryogenic piping and massive heavy lifts.
	Category Subtotal	23/25	Weighted Value: $(23 / 25) * 25 = 23.00$
2. Logistics Feasibility (Weight: 20%)	Transport Envelope	5	Supermodules weighing up to 4,000 tons are feasible via dedicated shipping slips.
	Route Constraints	4	Direct coastal access requires only minimal initial channel dredging.
	Barge/Port Access	5	Deepwater offloading facility adjacent to the plant foundation footprint.
	Heavy Lift/SPMT	5	Standardized, unobstructed roll-off paths support massive multi-line SPMT configurations.
	Seasonal Risks	3	Exposed to Atlantic hurricane seasons; requires careful window planning.
	Category Subtotal	22/25	Weighted Value: $(22 / 25) * 20 = 17.60$

3. Design & Standard. (Weight: 20%)	Equipment Freeze	4	Long-lead mixed refrigerant compressors must be locked early.
	Repeatability	5	Multi-train configurations leverage highly repeatable process configurations.
	3D Model Maturity	4	SmartPlant 3D models achieve 30% maturity at the early FEL-2 gate.
	Interface Complexity	3	Highly complex hookups across thousands of structural piping tie-ins.
	Scope Lock Change	4	Owner governance enforces strict penalties to prevent post-release engineering changes.
	Category Subtotal	20/25	Weighted Value: $(20 / 25) * 20 = 16.00$
4. Site & Climate (Weight: 15%)	Laydown Space	4	Spacious greenfield coastal plot provides sufficient space for staging.
	Working at Height	5	Modularizing standard pipe racks reduces hazardous elevated scaffolding needs.
	Extreme Climate	4	Sub-tropical heat and severe humidity depress open-air field labor productivity.
	Environmental Restraints	3	Wetland mitigation mandates limit the footprint of open-air site fabrication yards.
	Congestion Profile	5	Clean greenfield site minimizes physical interface issues with existing operations.
	Category Subtotal	21/25	Weighted Value: $(21 / 25) * 15 = 12.60$
5. Schedule Criticality (Weight: 10%)	Critical Path Comp.	5	Parallel yard fabrication cuts months off the primary construction path.
	Commissioning Window	4	Strict offtake windows dictate rigid operational startup timelines.
	Market Urgency	5	High spot-market pricing creates clear incentives for early product deliveries.
	Shutdown Limits	5	Greenfield project with no existing operations to interrupt.

	Cost of Delay	5	Delayed startup financial impacts easily exceed \$1M per day in lost revenue.
	Category Subtotal	24/25	Weighted Value: $(24 / 25) * 10 = 9.60$
6. Governance & Alignment (Weight: 10%)	Contract Readiness	4	Main EPC contract explicitly incorporates a split global modular execution model.
	Change Control	3	Historically moderate discipline; requires enhanced governance tracking.
	Modular Experience	5	The selected tier-1 EPC partner boasts an extensive track record with international modular builds.
	Yard Capability	4	Prequalified Asian megayards are locked into firm reservation agreements.
	Interface Management	4	Dedicated engineering interface teams run real-time automated BIM clashes.
	Category Subtotal	20/25	Weighted Value: $(20 / 25) * 10 = 8.00$

Weighted Diagnostic Calculation

Readiness Score = $23.00 + 17.60 + 16.00 + 12.60 + 9.60 + 8.00 = 86.8$

Strategic Executive Decision

Classification: Modularization Mandatory (Score: 86.8)

Executive Directive: Enforce a maximum modularization mandate (>70% of total structural/piping weight). Implement a dual-yard contracting strategy: secure specialized Asian megayards for the heavy 3,500-ton process supermodules and utilize domestic regional yards for standard utility racks and e-houses.

Appendix C

Heavy Industrial — Iron Ore Complex (Western Australia)

Project Context

A deep greenfield mine site located inland within the Pilbara region, paired with a dedicated export port facility. The project faces extreme labor shortages, high remote accommodation costs, severe desert heat, and strict local environmental compliance mandates.

Category	Criterion	Score	Operational Annotation / Executive Justification
1. Labor & Productivity (Weight: 25%)	Labor Availability	5	Severe structural labor shortage in the remote outback; requires high-cost FIFO flights.
	Wage Differential	5	Remote Australian field wages are significantly higher than Southeast Asian fabrication yard rates.
	Field Productivity	5	Extreme heat indices routinely drop field construction efficiency below 0.6.
	Union Constraints	3	Active union environments require comprehensive project alignment agreements.
	Safety Profile	5	Fly-in fly-out (FIFO) logistics and extreme remote environments introduce high safety exposure.
	Category Subtotal	23/25	Weighted Value: $(23 / 25) * 25 = 23.00$
2. Logistics Feasibility (Weight: 20%)	Transport Envelope	3	Port accepts large modules, but inland road haulage limits widths due to bridge clearances.
	Route Constraints	2	Critical Warning: 400km inland heavy-haul road route features tight turning radiuses.
	Barge/Port Access	4	Dedicated construction wharves support heavy roll-off operations at the port site.
	Heavylift /SPMT	4	Specialized heavy-haul transport contractors are available within Western Australia.
	Seasonal Risks	2	Wet seasons bring high cyclone risks, causing localized washouts and road closures.

	Category Subtotal	15/25	Weighted Value: $(15 / 25) * 20 = 12.00$
3. Design & Standardization (Weight: 20%)	Equipment Freeze	4	Heavy crushing and sizing equipment must be selected and detailed during early engineering.
	Repeatability	3	Port systems match mine layouts, but individual processing lines require custom engineering.
	3D Model Maturity	4	Advanced digital twin platforms support execution planning across remote teams.
	Interface Complexity	4	Conveyor runs and material transfer chutes feature linear, manageable interfaces.
	Scope Lock Change	4	Capital committees enforce strict limits on late engineering design changes.
	Category Subtotal	19/25	Weighted Value: $(19 / 25) * 20 = 15.20$
4. Site & Climate (Weight: 15%)	Laydown Space	5	Remote desert locations offer unconstrained geographic staging and laydown acreage.
	Working at Height	4	Prefabricated screening structures significantly reduce elevated assembly work on site.
	Extreme Climate	5	Summer temperatures routinely exceed 45°C, stopping open-air field work.
	Environmental Restraints	4	Remote site footprints are tightly controlled to minimize impacts on heritage sites.
	Congestion Profile	5	Greenfield site layout allows unconstrained construction vehicle access.
	Category Subtotal	23/25	Weighted Value: $(23 / 25) * 15 = 13.80$
5. Schedule Criticality (Weight: 10%)	Critical Path Comp.	4	Mining production schedules are timed to capture open global commodity demand cycles.
	Commissioning Window	4	First-shipment milestones are tied to binding joint-venture investment agreements.
	Market Urgency	4	High-grade ore product commands strong spot prices during market upswings.

	Shutdown Limits	5	Greenfield infrastructure asset with no existing operations to interrupt.
	Cost of Delay	5	Delayed operational startup costs exceed \$750k per day in unrealized cash flow.
	Category Subtotal	22/25	Weighted Value: $(22 / 25) * 10 = 8.80$
6. Governance & Alignment (Weight: 10%)	Contract Readiness	4	EPCM delivery models use dedicated, discrete modular fabrication packages.
	Change Control	4	Automated digital stage-gate systems manage design variances tightly.
	Modular Experience	5	Major Australian mining companies possess deep institutional expertise with modular builds.
	Yard Capability	4	Prequalified modular yards across Indonesia, Malaysia, and China are available.
	Interface Management	4	Standardized mechanical and structural interfaces ensure reliable fit-up.
	Category Subtotal	21/25	Weighted Value: $(21 / 25) * 10 = 8.40$

Weighted Diagnostic Calculation

Readiness Score = $23.00 + 12.00 + 15.20 + 13.80 + 8.80 + 8.40 = 81.2$

Strategic Executive Decision

Classification: Modularization Mandatory (Score: 81.2)

Executive Directive: Enforce a bifurcated modular strategy. Drive a maximum supermodule strategy (up to 2,500 tons) for the coastal port materials-handling facility and car dumpers. For the inland mine site, restrict maximum module weights to 150 tons to clear inland transport route constraints. All inland processing structures must be optimized as transportable linear skids or open-truss assemblies.

Appendix D

Commercial — AI Hyper Data Center (Austin, Texas)

Project Context

A fast-track AI data center development featuring high structural density. The project requires massive power infrastructure and complex water-cooling loops. It faces tight schedule constraints driven by technology lease commitments, within a busy suburban market.

Category	Criterion	Score	Operational Annotation / Executive Justification
1. Labor & Productivity (Weight: 25%)	Labor Availability	3	Austin market is highly active; skilled data center E&I craft labor is constrained.
	Wage Differential	2	Texas open-shop labor rates remain competitive with domestic prefabrication yards.
	Field Productivity	4	Complex, high-density cleanroom and power hookups suffer from site congestion.
	Union Constraints	5	Minimum union constraints; flexible off-site fabrication options are readily available.
	Safety Profile	3	Standard commercial risks; high-voltage testing presents the primary safety exposure.
	Category Subtotal	17/25	Weighted Value: $(17 / 25) * 25 = 17.00$
2. Logistics Feasibility (Weight: 20%)	Transport Envelope	4	Standard modular e-houses and skid sizes fit comfortably on interstate highways.
	Route Constraints	3	Suburban road networks require standard wide-load escort permits.
	Barge/Port Access	1	Inland Site: No maritime access available; completely reliant on road transport.
	Heavylift/SPMT	4	Standard high-capacity mobile hydraulic cranes are available in the local market.
	Seasonal Risks	4	Central Texas weather allows for reliable year-round road transport operations.

	Category Subtotal	16/25	Weighted Value: $(16 / 25) * 20 = 12.80$
3. Design & Standardization (Weight: 20%)	Equipment Freeze	2	Risk Factor: Rapidly changing AI chip architectures can force late cooling design changes.
	Repeatability	5	Data hall layouts, power blocks, and cooling skids are highly standardized.
	3D Model Maturity	5	High-fidelity, fabrication-ready 3D BIM models are standard for data centers.
	Interface Complexity	4	Standardized, well-defined electrical busway and structural manifold connections.
	Scope Lock Change	2	Technology groups often push for late design changes to capture computing updates.
	Category Subtotal	18/25	Weighted Value: $(18 / 25) * 20 = 14.40$
4. Site & Climate (Weight: 15%)	Laydown Space	2	Restricted suburban footprint with limited space for on-site material staging.
	Working at Height	2	Low-rise structural profiles; minimal high-altitude assembly required.
	Extreme Climate	3	High summer heat peaks require indoor or night-shift work schedules.
	Environmental Restraints	4	Noise ordinances and dust controls limit heavy on-site fabrication work.
	Congestion Profile	3	Multiple concurrent trades on site create significant workspace congestion.
	Category Subtotal	14/25	Weighted Value: $(14 / 25) * 15 = 8.40$
5. Schedule Criticality (Weight: 10%)	Critical Path Comp.	5	First-to-market speed drives competitive advantages in securing AI cluster leases.
	Commissioning Window	5	Power energized dates are tied to binding tenant operational deadlines.
	Market Urgency	5	High demand for specialized AI computing capacity yields immediate revenue generation.

	Shutdown Limits	5	New greenfield facility build; no active computing infrastructure to disrupt.
	Cost of Delay	5	Late delivery penalties and lost lease revenue exceed \$500k per day.
	Category Subtotal	25/25	Weighted Value: $(25 / 25) * 10 = 10.00$
6. Governance & Alignment (Weight: 10%)	Contract Readiness	4	Progressive Design-Build contracts cleanly support off-site manufacturing integration.
	Change Control	2	Highly fluid technology requirements demand rigid corporate change governance.
	Modular Experience	4	Mission-critical project teams possess deep experience with modular power blocks.
	Yard Capability	5	Specialized domestic data center integration yards are operational across Texas.
	Interface Management	4	Clean, multi-discipline BIM coordination processes track all physical connections.
	Category Subtotal	19/25	Weighted Value: $(19 / 25) * 10 = 7.60$

Weighted Diagnostic Calculation

Readiness Score = $17.00 + 12.80 + 14.40 + 8.40 + 10.00 + 7.60 = 70.2$

Strategic Executive Decision

Classification: Modularization Advantageous (Score: 70.2)

Executive Directive: Deploy a targeted, high-density sub-system modular strategy. The structural shell and building envelope should be fast-tracked using pre-cast concrete panels. Concurrently, mandate off-site modular prefabrication for all complex technical spaces: supply all power infrastructure as pre-commissioned E-Houses, and configure all cooling infrastructure into ready-to-connect liquid cooling blocks. Establish a strict engineering gate control process to protect the off-site manufacturing schedule from late technology adjustments.

For Further Reading – Other Executive Insights

- Craft Training for Modular Construction
- Digital Passports Training for Modular Construction
- Golden Thread
- Modular Construction Contract Consideration
- Spare Parts in Modular Construction
- Modular Construction Transportation Risks
- Economic & Schedule Trade-Offs in Modular vs. Stick-Built Execution

About the Author

Bob Prieto was elected to the National Academy of Construction in 2011. He is a senior executive who is effective in shaping and executing business strategy and a recognized leader within the infrastructure, engineering, and construction industries. Bob received the 2024 ASCE OPAL Award (Outstanding Projects and Leaders) for his Outstanding Lifetime Achievement in Management.

Although the author and NAC have made every effort to ensure accuracy and completeness of the advice or information presented within, NAC and the author assume no responsibility for any errors, inaccuracies, omissions or inconsistencies it may contain, or for any results obtained from the use of this information. The information is provided on an “as is” basis with no guarantees of completeness, accuracy, usefulness or timeliness, and without any warranties of any kind whatsoever, express or implied. Reliance on any information provided by NAC or the author is solely at your own risk.